MANITOWOC ICE
2110 SOUTH 26TH STREET, MANITOWOC, WI 54220
800-545-5720
WWW.MANITOWOCICE.COM

Instruction Sheet

Subject: 000014344 Indigo Dual Evaporator Bin Switch & Water Trough Kit

Replacement Bin Switch & Water Trough Instructions

⚠Warning

Authorized Service Representatives are obligated to follow industry standard safety procedures, including, but not limited to, local/national regulations for disconnection / lock out / tag out procedures for all utilities including electric, gas, water and steam.

⚠DANGER

Disconnect electric power to the ice machine at the electric switch box before proceeding. Failure to disconnect the power at the main power supply disconnect could result in serious injury or death. The power switch DOES NOT disconnect all incoming power.

This kit is used to minimize interference issues on Indigo dual evaporator ice machines.

Kit Components:

PART NUMBER	DESCRIPTION	QTY
000013372	.25X .032" MALE INS TERMINAL	2
000013373	.25X .032" FEMALE INS TERMINAL	2
000007888	BIN SWITCH	2
000014343	WATER TROUGH	1
000002287	FOAM TAPE	

Step 1 Disconnect power to the ice machine and remove required panels to access bin switches and water trough.

Right Bin Switch

Step 2 Replace right bin switch with part supplied in kit (000007888). No modifications are required.

Left Bin Switch:

Step 3 Cut the bin switch wire 4" from the bin switch. Remove bin switch from ice machine and discard.



Step 4 Strip 2" of outer jacket and .25" of insulation from the black and red bin switch wires leading to the control board.

Step 5 Crimp two male insulated terminals (000013372) to the stripped wires.

Step 6 Shorten the second replacement bin switch wires (00007888) to 6"-8" (enough to allow easy connection without excess slack). Strip 2" of outer jacket and .25" of bin switch wire insulation and then crimp female terminals (000013373) to the stripped wires.

Step 7 Feed bin switch wires through bulk head and connect male and female terminals.



Continued Next Page

Step 8 Use supplied foam tape (000002287) to protect the terminals from condensation. Use the second piece if needed,overlapping by at least ½ inch.



Step 9 Replace water trough with kit trough (000014343).

Step 10 Reinstall side panels, reconnect power and test ice machine operation.

Step 11 Sanitize the ice machine when testing is complete.